

11 Hartmann Street
Meyerton
Mantlani

P O Box 6142
Meyerton 2107
Tel: (011) 888-2400 Fax: (011) 888-1656



REQUEST FOR QUOTATION

QUOTATIONS WILL BE EVALUATED ON THE 80/20 POINT SCORING SYSTEM. 80 POINTS WILL BE ALLOCATED TO PRICE AND THE REMAINING 20 POINTS WILL BE ALLOCATED FOR BBBEE AND PREFERENTIAL PROCUREMENT
ALL SUPPLIERS RESPONDING TO QUOTATIONS SHOULD BE REGISTERED ON CENTRAL SUPPLIER DATABASE (CSD)

JW CONTACT PERSON: Nompumezo e-mail address: nompumezo.mramba@water.co.za.....

TELEPHONE NUMBER: 011 888 1656, FAX NO: 086 611 8167

14-Jun-19	18:00
08 June 2019	
7 : DAYS	

OPERATIONS SOUTH ALE **Afhehl Meshivhunde**

JW323NM 2019 KHAYELITSHA PIPE

SITE MEETING : 13 June 2019 Thursday


TIME : 11:00

Venue: Near Jeppestown Cnr City and Suburban Road and Jules

Opposite Maim Informal Settlement

Contact: 072 638 4108 Afhehl

1	<p>Prospective tenders are requested to quote for the installation of Four Communal Stand pipe with drainage system at Khayelitsha Informal Settlement to dispose of the waste water run-off from communal standpipes into intercepting desludging tanks (as per the attached sketch). The drainage system must be constructed using normal 200mm Class 34 or 400 Kpa underground Pvc sewer pipe with the spigot and socket joining system and large radius bends (push fit type) with inspection plates.</p> <p>The two intercepting desludging tanks must be accessible to the Desludging Combo trucks. Manhole chambers (1000mm diameter) also to be constructed (to JW specifications) at suitable points along the line between the 2 intercepting tanks as shown on the attached sketch. Suitable grids/screens to be placed at the entry point of the drainage system to prevent litter entering the line and intercepting tanks.</p> <p>Contractors to bring their measuring apparatus to the site meeting as no linear measurements are provided on the attached sketch.</p>	1			
	Quotations should be valid for 60 days				
	NB: All suppliers responding to Rfq's should use their own company letter head not JW Rfq Template AND MAKE SURE THEIR EMAIL ADDRESS IS VISIBLE ON THEIR QUOTATION.				
OFFICIAL STAMP					
<p>AUTHORISED BY:</p> <p>SIGNATURE:</p> <p>DATE:</p>					
<p>CONDITIONS</p> <p>1. QUOTATIONS RECEIVED AFTER CLOSE OF BUSINESS ON THE CLOSING DATE WILL NOT BE ACCEPTED.</p> <p>2. QUOTATIONS WITHOUT BRAND NAMES WHERE REQUIRED WILL NOT BE ACCEPTED.</p> <p>3. PRICES QUOTED MUST BE AS PER THE UNIT INDICATED AND BE EXCLUDED OF VAT.</p> <p>4. QUOTATIONS WITHOUT THE SUPPLIER'S AUTHORIZED SIGNATURE WILL NOT BE ACCEPTED.</p> <p>5. ACCEPTANCE OF A QUOTATION WILL BE SUBJECT TO JOHANNESBURG WATER'S SUPPLY CHAIN POLICY.</p>					

	Document title :	Minimum SHE Requirements for Construction Related RFO projects		
	Revision	00	Author:	OHS: Projects
	Effective Date	January 2017		Pages:
				10

1. SCOPE OF WORK:

Installation of Four Communal Stand pipe with drainage system at Khayelitsha Informal Settlement

2. PURPOSE

The aim of the SHE specification is to ensure that any contractor which is appointed by Johannesburg Water to conduct any work complies with the SHE requirements of the SHE specification and any other legislative requirement applicable to the contract scope.

3. APPLICABILITY

This document is applicable to all contractors and suppliers conducting contractual activities for and on behalf of Johannesburg Water.

4. APPOINTMENTS

The contractor and its appointed sub-contractor must make the relevant legislative and non-statutory appointments, which must be maintained valid for the entire contract duration.
All appointees shall be suitably trained and found to be competent for the responsibilities there are assigned for.
Copies of all relevant appointments and the relevant competence certificates must be kept in the relevant SHE file.

5. INSURANCE

The contractor and all its appointed sub-contractor(s) shall be registered with an appropriate compensation commissioner and have a valid letter of good standing from commissioner. The contractor is responsible for ensuring the Letter of Good Standing is valid for the entire duration of the project/contract. A copy of the letter of Good Standing must be kept in the SHE file.

6. COSTING FOR SHE REQUIREMENTS

The contractor is responsible for ensuring that SHE costing is taken into consideration for the entire project/contract as this will ensure they comply with the SHE legislative requirements

7. INDUCTION

An initial induction shall be done with key personnel to familiarize them with the requirements on site and for compiling the SHE file.
Once labourers are appointed JW will conduct an induction on SHE requirements, and the contractor is also required to conduct their company specific induction.



Document title : Minimum SHE Requirements for Construction Related RfQ projects	Revision	00	Author:	OHS Projects
	Effective Date	January 2017	Pages:	10

8. SUBMISSION OF SAFETY FILE

- Once appointed the contractor can submit their safety file for approval.
- Approval will be granted when the critical items have been sufficiently addressed.

9. RISK ASSESSMENT

- Every Contractor who has been appointed contractually to conduct work for Johannesburg water shall do compile a baseline risk assessment prior to starting with work, subject to the approval of the Client.
- Thereafter the task based risk assessments will be done daily with every task being done.

10. SAFE WORKING PROCEDURES / METHOD STATEMENTS

The following method statements / safe working procedures must be compiled:

- Use of power tools

11. MEDICAL SCREENING REQUIREMENTS

- The contractor shall ensure that a medical surveillance programme is implemented for all employees.
- The medical examination shall be conducted in line with the employee job profile/job description.
- A valid medical fitness certificate must be submitted together with the SHE File for approval for all employees who will be doing work for Johannesburg Water.
- Any employee(s) who are declared conditionally fit must be provided with employment which does not aggravate their medical condition as to endanger themselves or other employees.
- The following tests shall be done:
 - Audiograms.
 - A cardio-respiratory examination
 - Lung function tests.
 - Eye/ sight tests.
 - A general physical examination.
 - A review of previous medical history.
 - Blood pressure tests
 - Glucose tests

12. TOOLBOX TALKS

- The contractor shall ensure they conduct toolbox talks with their employees on a weekly basis and records of these must be kept in the SHE file.



Document title:	Minimum SHE Requirements for Construction Related RfQ projects		
	Revision	00	Author: GMS Projects
Effective Date	January 2017		Pages: 10

- The objective of toolbox talks should be to communicate relevant site information to assist in improvement of occupational health and safety performance.
- Employees must acknowledge the receipt of toolbox talks and this record must also be kept in the SHE file.

13. PERSONAL PROTECTIVE EQUIPMENT (PPE)

- Contractor must issue their employees SABS approved PPE. A copy of the PPE issue register signed by the employee issued with the PPE must be kept in the SHE file.
- Contractor supervisor are required to conduct continuous inspections of the PPE issued to their employees to ensure that they are still in good condition to be used by the employee or they still comply with manufacture requirements.
- The contractor is responsible for ensuring that employees are trained on the safe use of the PPE issued to them, how to maintain it and the limitations of the PPE.
- NO SHORTS OR DRESSES WILL BE ALLOWED ON SITE

14. WORKPLACE SIGNAGE

- Appropriate symbolic signage must be displayed where it is required by legislation.
- Appropriate warning, mandatory and information signs must be placed where required.
- All signs must comply to SANS/SABS requirements.
- Contractors shall use mandatory and prescribed symbolic safety signs at their lay down and site areas.

15. INCIDENT REPORTING AND INVESTIGATION

- All incidents shall be reported to the Client before the end of the shift or within 24hrs of occurrence.
- Section 24 incidents shall be reported to DOL using the prescribed format.
- The contractor shall develop an incident management procedure and communicate with all employees.

16. NOTIFICATION OF CONSTRUCTION WORK

- The contractor shall notify the DOL in the prescribed format of the intended work prior to work.

17. PUBLIC HEALTH AND SAFETY



Document title:	Minimum SHE Requirements for Construction Related RFD projects		
	Revision	00	Author: OHS Projects
Effective Date	January 2017		Pages: 10

The Principal Contractor is responsible for ensuring that non-employees affected by the construction work are made aware of the dangers likely to arise from the construction work as well as the precautionary measures to be observed to avoid or minimise those dangers. This includes:

- Non-employees entering the site for whatever reason;
 - The surrounding community; and
 - Passers-by the site.
- The Principal Contractor shall organize the site in such a manner that pedestrians and vehicles can move safely and without risks to health, including sufficient and suitable traffic routes and safe walkways with relevant signage.

18. ACCOMMODATION ON SITE

No employees shall be accommodated on site.

19. WELFARE FACILITIES

The provision of toilets for each sex is required in terms of the National Building Regulations and Construction Regulation 28. Chemical toilets are allowed instead of the water borne sewerage type. Toilets have to be provided at a ratio of 1 toilet per 30 workers. The Principal Contractor shall provide flushing toilets on the construction premises.

- At least cold-water showers for each sex have to be provided at a ratio of 1 shower per 15 workers.
- Some form of screened off changing facility must be provided separately for each sex.
- Some form of eating facility sheltered from the sun, wind and rain must be provided.

The employer needs to provide his employees with the following:

- Potable water for drinking;
- Water and soap for hand washing
- Toilet paper

20. HAND TOOLS

The Principal Contractor must inspect all hand tools before it is brought onto the site.

- As far as possible all hand tools must be numbered and placed on register to be inspected monthly by a person designated to do so.
- Any tools found to be in an unsafe condition must immediately be removed from service and either discarded or rectified.



Document title :	Minimum SHE Requirements for Construction Related RFD projects		
	Revision	00	Author: EMS Project
Effective Date	January 2017		
	Pages:	10	

- No chisels with "mushroomed" heads must be used.
- No hammer shall be used with a cracked or damaged handle.
- All files must be fitted with handles.
- All trolleys, pushcarts, etc. used on site must be identifiable, placed on register and inspected at least once every month.
- Non-sparking tools must be used in areas where the risk of fire or explosion is present.
- No homemade hand tools are allowed on the project.
- All tools shall be attached to a suitable lanyard when utilised in elevated positions

21. EMERGENCY MANAGEMENT

- The Principal Contractor must appoint a competent person to act as emergency controller and/or coordinator.
- The Principal Contractor must conduct an emergency identification exercise and establish what emergencies could possibly develop.
- He must then develop detailed contingency plans and emergency procedures, taking into account any emergency plan that Johannesburg Water SOC Ltd may have in place.
- In the event where a contractor incorporates the services of a 3rd party service provider for the provision of Emergency Response Services, the following criteria must be met:
 - Identification of 3rd party emergency response services (organization & contact details);
 - Notification of contractor to 3rd party emergency response service of incorporation of services into contractor's emergency response plan (written agreement / signed letter).
- The Principal Contractor and the other contractors must hold regular practice drills of contingency plans and emergency procedures to test them and familiarise employees with them.

First-aid

- The Principal Contractor must provide first-aid equipment (including a stretcher) and have qualified first-aiders(s) on site as required by General Safety Regulations promulgated in terms of the Occupational Health and Safety Act (Act no. 85 of 1993).
- The contingency plan of the Principal Contractor must include arrangements for the speedy and timely transporting of injured and/or ill person(s) to a medical facility or of getting emergency medical aid to person(s) who may require it.
- The Principal Contractor must have written arrangements in place with his other contractors regarding the responsibility of the other contractors towards their own injured and/or ill employees.



Document title:	Minimum SHE Requirements for Construction Related Work		
	Revision	00	Author: OHS Projects
Effective Date	January 2017		
Pages:	10		

22. HAZARDOUS CHEMICAL SUBSTANCES

The Principal Contractor must ensure that:

- Employees receive the necessary information and training to be able to use and store hazardous chemical substances safely;
- Employees obey lawful instructions regarding:

- The wearing and use of protective equipment
- The use and storage of hazardous chemical substances
- The prevention of the release of hazardous chemical substances
- The wearing of exposure monitoring and measuring equipment
- The cleaning up and disposal of materials containing hazardous chemical substances
- Housekeeping, personal hygiene and the protection of the environment

- The risk assessments required in terms of Construction Regulation include employee exposure to hazardous chemical substances and that the necessary measures be taken to protect persons from being detrimentally affected by hazardous chemical substances present or used in the workplace;

- Suppliers provide the necessary information in the form of a material safety data sheet regarding a hazardous chemical substances required to ensure the safe use and storage of that substances;

- An up-to-date list is kept on site of hazardous chemical substances stored and used together with the material safety data sheet of the hazardous chemical substances;

- Hazardous chemical substances containers be clearly marked with the contents and main hazardous category e.g. "Flammable" or "Corrosive" and the reference number of the hazardous chemical substances on the list indicated above;

- Hazardous chemical substances, for example asbestos dust, are not cleared by using compressed air but should be vacuumed;

- No person eats or drinks in a hazardous chemical substances workplace; and
- Hazardous chemical substances waste is disposed of safely in terms of hazardous waste disposal requirements.

MSDS's to be in 16 point format- available on site

23. FIRE PREVENTION AND PROTECTION

The Principal Contractor must ensure that:

- The risk of fire is avoided;
- Sufficient and suitable storage for flammables is provided;


- Upon completion of the project the SHE file shall be returned to the Client for retention and close out.

25. PROJECT COMPLETION

- Weekly inspections and monthly audits will be conducted on site.

24. COMPLIANCE MONITORING

- A siren or alarm is fitted which is clearly audible to all persons on site.
- left behind; and
- Roll call is held after evacuation to account for all personnel and ensure that no-one has been
- Evacuation is practiced to ensure that all persons are evacuated timeously;
- Evacuation assembly points are demarcated;
- Emergency escape routes are kept clear at all times and clearly marked;
- Employees are informed regarding emergency evacuation procedures and escape routes;
- deal with fires and other emergencies;
- A sufficient number of employees are appointed and trained to act as an emergency team to
- to extinguish a fire;
- All employees are instructed in the use of the fire fighting equipment and know how to attempt
 - Annual inspection and service by an accredited service provider
 - Regular inspection of fire equipment by a competent person appointed in writing and keeping a register
- Maintenance must include:
 - in good working order.
 - Adequate and suitable fixed and portable fire fighting equipment is provided and maintained
 - Adequate ventilation is maintained
 - Good housekeeping is maintained to prevent the accumulation of unnecessary combustibles
 - Flameproof switches and fittings are to be used in the flammable atmosphere
 - tools that produce sparks
 - No grinding, cutting and shaping of ferrous metals is allowed using electrically driven power
 - Only spark-free hand and power tools are used
- work permits
- Welding and flame cutting is only allowed under controlled conditions that includes written hot
- Notices prohibiting smoking are displayed and enforced
- in the workplace, for example:
 - Sources of ignition are removed wherever flammable or highly combustible material is present

 Johannesburg Water	Document title:	Minimum SHE Requirements for Construction Related RFP Projects		
	Revision	00	Author:	OHS Projects
Effective Date	January 2017	Pages:	10	



Document title:	Minimum OHS Requirements for Construction Related Workplaces
Revision	00
Effective Date	January 2017
Author:	OHS: Projects
Pages:	10

Project details

Project Scope: DESIGN AND INSTALLATION OF PRIMING CHAMBER

Dept / Site / Department: NORTHERN WWTW

Estimated duration: TBC

Documents required

Letter of Good Standing	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
SHE plan	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
Risk Assessment	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
Safe working Procedures	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
Notification of Construction work	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
Inspection registers	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>

Items required before starting

Medicals	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
Vaccinations	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>	N/A	<input type="checkbox"/>
PPE (boots, hard hats, overall)	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
Induction	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
Approval from OHS	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>

APPOINTMENTS AND COMPETENCIES

Construction Supervisor	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
CV (and/ certificates)	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
Safety Officer	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input type="checkbox"/>
Appointment	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input checked="" type="checkbox"/>
CV (and/ certificates)	Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	N/A	<input checked="" type="checkbox"/>

NB* Other appointments will be based on the number of employees on site as required by law.

CONTRACT MANAGER			
NAME	DESIGNATION	DATE	SIGNATURE
CONTRACT SUPERVISOR			
NAME	DESIGNATION	DATE	SIGNATURE
WITNESS (1)			
NAME	DESIGNATION	DATE	SIGNATURE
WITNESS (2)			
NAME	DESIGNATION	DATE	SIGNATURE


Signed at on this Day of 20.....

I, the undersigned, hereby acknowledge that I have obtained copies of the following listed documentation and confirm that I fully understand the contents thereof and the consequences of non-compliance. The Contractor furthermore reiterates its commitment to compliance of the requirements contained within the following provided documentation:

- Johannesburg Water SOC Ltd, Safety, Health & Environmental (SHE) Specification, Annexure 1: Baseline risk assessment conducted for or on behalf of Johannesburg Water SOC Ltd;

CONTRACTOR

RETURNABLE ANNEXURE A: ACKNOWLEDGEMENT OF SHE SPECIFICATION & ANNEXURES

	Document title:	Minimum SHE Requirements for Construction Related RFQ projects		
	Revision	00	Author:	GHS Projects
	Effective Date	January 2017	Pages:	10

HEALTH, SAFETY & ENVIRONMENTAL (SHE) SPECIFICATION: BASELINE RISK ASSESSMENT



Johannesburg Water

PROJECT NUMBER: RFQ

PROJECT LOCATION: Khayelitsha Informal Settlement

PROJECT DESCR: Installation of Four Communal Stand pipe with drainage system at Khayelitsha Informal Settlement

POSSIBLE RISKS FOR THIS PROJECT

Task	Hazard	Risk	Consequence	Rating	Controls
Transportation of material to site	<ul style="list-style-type: none"> ✓ Unsafe road conditions ✓ Un-road worthy vehicles ✓ Equipment and material not safely secured ✓ Incompetent drivers ✓ Driving under the influence of alcohol ✓ Inclement weather ✓ Speeding 	<ul style="list-style-type: none"> ✓ Overturning vehicles ✓ Vehicle collisions 	<ul style="list-style-type: none"> ✓ Injuries ✓ Property damages ✓ Third party liability 	M	<ul style="list-style-type: none"> ✓ Adherence to the speed limit ✓ Only competent/ authorised drivers should operate the vehicle ✓ Inspection of vehicles ✓ Equipment and material to be properly secured ✓ Alcohol testing to be done ✓ The road to be paved to prevent accidents ✓ Traffic control to be implemented to avoid collisions
	<ul style="list-style-type: none"> ✓ Faulty machinery ✓ Poor ergonomics ✓ Equipment (suspended load) falling on employees ✓ Unsafe slings and guide ropes ✓ uneven surface 	<ul style="list-style-type: none"> ✓ Hands can be caught in between materials ✓ Obstructed walkways by materials ✓ Unsafe stacking of materials ✓ Inhalation 	<ul style="list-style-type: none"> ✓ Hand injuries ✓ Back injuries ✓ Respiratory illnesses 	M	<ul style="list-style-type: none"> ✓ The correct PPE must be worn ✓ Designate the stacking areas and put signs ✓ Stacking and storage inspector must be appointed and in charge
Digging trenches	<ul style="list-style-type: none"> ✓ Dust 	<ul style="list-style-type: none"> ✓ Inhalation 	<ul style="list-style-type: none"> ✓ Respiratory illnesses 		<ul style="list-style-type: none"> ✓ Employees must be provided with dust masks.
Use of hand tools	<ul style="list-style-type: none"> ✓ Damaged tools 	<ul style="list-style-type: none"> ✓ Using the wrong tool for the job ✓ Using damaged 	<ul style="list-style-type: none"> ✓ Injuries 		<ul style="list-style-type: none"> ✓ All tools must be visually inspected before use.

		tools ✓ Lack of skill		<ul style="list-style-type: none"> ✓ Faulty tools must be replaced. ✓ Use the right tool for the job ✓ Use tools according to manufacturer's specifications. 	
Drilling and fitting	✓ Drilling sharp metal fibers	✓ Eye penetration	✓ Injuries	M	<ul style="list-style-type: none"> ✓ Works foreman to issue appropriate PPE for the task (Safety goggles and gloves)
	✓ Drill usage	✓ Cuts	✓ Damaged hearing		
	✓ High level of noise	✓ Vibrations			
	✓ Work Temperature	✓ Employees working on high or low temperature	✓ Ill health		<ul style="list-style-type: none"> ✓ Monitor for Heat / Cold stress ✓ Provide fluids to prevent worker dehydration. ✓ Establish work/rest schedule
	✓ Flying debris	✓ Eye penetration	✓ Eye injuries/blindness		<ul style="list-style-type: none"> ✓ Safety goggles shall be worn by employees when cutting steel
	✓ High Noise Levels	✓ Expose to high noise level area	✓ Damaged hearing	M	<ul style="list-style-type: none"> ✓ Use hearing protection when exposed to excessive noise levels (greater than 85 dB over an 8-hour work period) ✓ Rotate the employees exposed to excessive noise levels.
Welding	✓ Fumes	✓ Inhalation	✓ Respiratory problems	M	<ul style="list-style-type: none"> ✓ Wear respiratory protection
	✓ Sparks	✓ Contact with skin	✓ Skin burns		
	✓ Sparks	✓ Fire	✓ Damage to property		
	✓ Welding arc	✓ Starring welding arc	✓ Eye irritation		<ul style="list-style-type: none"> ✓ Safety goggles to be worn
Concrete works	✓ Poor quality material	✓ Unstable structure	✓ Serious injuries	M	<ul style="list-style-type: none"> ✓ Only good quality material should be used using the designer's specifications.
	✓ Trying to save time	✓ Contact	✓ Collapse of structure		
	✓ Exposed skin				

Working outside	<ul style="list-style-type: none"> ✓ Sunlight 	<ul style="list-style-type: none"> ✓ Burns ✓ Exposure 	<ul style="list-style-type: none"> ✓ Dermatitis ✓ Skin cancer ✓ Dehydration ✓ Heatstroke 	[REDACTED]	<ul style="list-style-type: none"> ✓ Concrete should be left to cure in ambient conditions to attain design strength ✓ Provide sun hats and sunscreen to employees ✓ Provide sufficient water to drink ✓ Provide rest periods for every 1hr worked
Moving traffic	<ul style="list-style-type: none"> ✓ Sharp curve ✓ No fence 	<ul style="list-style-type: none"> ✓ Bumping into the station 	<ul style="list-style-type: none"> ✓ Damages to the pump station 	[REDACTED]	<ul style="list-style-type: none"> ✓ Put signage to slow down traffic ✓ Use delineators to alert motorists and for visibility at night and when it's dark ✓ Fencing of the pump station
Storage of HCS	<ul style="list-style-type: none"> ✓ Burning or fires on site ✓ Improper labelling of chemical containers 	<ul style="list-style-type: none"> ✓ Property damage ✓ Accidental consumption of flammable liquids 	<ul style="list-style-type: none"> ✓ Trip and fall injuries ✓ Personal injuries 	M	<ul style="list-style-type: none"> ✓ A well ventilated cage may be used for storage of all the HCS and flammables ✓ Keep register of all HCS ✓ Label containers correctly ✓ Display HCS signage
Reinstatement of the surface	<ul style="list-style-type: none"> ✓ Inadequate compaction ✓ Construction refuse ✓ Inadequate re-surfacing High ✓ Ground collapse ✓ hydraulic/pneumatic pressures 	<ul style="list-style-type: none"> ✓ Uneven surfaces 	<ul style="list-style-type: none"> ✓ Trip and fall injuries ✓ Personal injuries 	[REDACTED]	<ul style="list-style-type: none"> ✓ Compaction to specified standard. ✓ Site cleared of debris and refuse. ✓ Re-surface appropriately. ✓ Do not leave gaps in turf or leave uneven surface. ✓ Erect fence around hazardous areas until restored and safe. ✓ Ensure plugs and compressors are installed and secured against movement. ✓ Release air before removing plugs. ✓ Clear area of pipe ends being tested.

RISK ASSESSMENT MATRIX

Likelihood	Consequences				
	Insignificant (minor problem easily handled by normal day to day processes	Minor (Some disruption possible e.g. damage equal to R150k	Moderate (significant time / resources required. E.g., damage equal to R500k	Major (Operations severely damaged. E.g., damages equal to R1m	Catastrophic (business survival is at risk. Damage equal to R5m – 10m
Almost certain (90% chance)					
Likely (between 50-90%)	Moderate				
Moderate (between 10-50%)		Moderate			
Unlikely (between 3-10%)			Moderate		
Rare (<3%)				Moderate	
					LOW